



SEQUENCE OF OPERATION

1. Lighting and fan are manually controlled On/Off with occupancy sensor switch.
2. Lighting and fan will auto Off within 20 minutes of occupants leaving.

DESIGN CONSIDERATIONS

- Demand Response, time scheduling and remote programming functions may be enabled by using DLM product with LMBC-300 Network Bridge connectivity for this space.

BILL OF MATERIALS

PW-301 (1)	Wallbox PIR Occupancy Sensor
------------	------------------------------

CODE REQUIREMENTS

9.4.1.1(a)	Local Control Device
9.4.1.1(h)	Auto Full Off
6.4.3.4.4	Ventilation Fan Controls